

REMOVAL & RECONSTRUCTION
 NOV 07 1994
 COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 28

For corners in

Lenawee Located In: Corner Code #
 (County)

1. Public Land Survey T-6-S R-4-E D-1
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

FILED

10:56 AM

OCT 28 1994

LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 26 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1				●									
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner was not set of GLO Survey
 March 1887, James Blair dug for corner. Set stake, dishes and glass on line between NE & NW corner of Section 5, T6S-R4E in line with fence running South.
 J.L. Richard records from early 1900's called for slate, dishes and glass and iron added in 1923.
 W.E. Frazier records show the corner was found April 3, 1943, boat spike added.
 October 30, 1964, I found boat spike 12" deep and raised to surface with iron pipe.
 September 12, 1980, Werner Sommer found the iron pipe and recorded it in L. 4, P 341.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11-9-93 & 12-13-93, Found 3/4" re-rod in monument box. The road was excavated to a depth of 2'± during construction 2 years ago, and most witnesses were destroyed.
 Used remaining witnesses retraced surveys done previously and found re-rod to be 0.03 South and 0.10 East of original location. Removed re-rod and set 3/4" X 3' iron pipe capped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the corner.

Plat monument South 59.95
 Dbl. hd. nail & disc in Elec pole S 10° W 84.44
 Dbl. hd. nail & disc in Elec pole N 65° E 172.89
 NW corner of house foundation S 30° E 122.80
 SE corner of brick house N 60° W 246.31



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-29-94

Signed by Glenn E. Richard Date Oct 10, 1994
 Glenn E. Richard

Surveyor's Michigan License No. 13040