

APR 01 1996

LAND CORNER RECORDATION CERTIFICATE

LIBER 001 PAGE 82

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For comers in

Lenawee Located In: Corner Code #  
 (County)

1. Public Land Survey T-6-S R-4-E K-9  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

FILED

NOV 22 1995

11:56 AM

LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on September 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 15-20, 1819, Joseph Fletcher, D.S., set post Beech 14 N 33 E 10 Scyamore 30 S 42 W 48 October 1841, Section 24 and May 1843, Section 25 were subdivided by S.C. Boughton, County Surveyor (monuments were not described).  
 Record of J.L. Richard from early 1900's show he found irons and stake. Fence post south 26' 6" Maple N 48±W 36 1/2'  
 November 1954 K.L. Suydam set spike from J.L. Richard witnesses.  
 August 1964, I found small boat spike in pavement and replaced it with an iron pipe.  
 February 1973, I found the iron pipe and recorded it in Liber 2, Page 323.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 14, 1995, Found iron pipe under 4" of asphalt. Dug another 18" to get iron pipe out and found bricks and several small stones. Also had indication of another iron deeper. Set 3/4" X 3' gas pipe in place of the iron pipe and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box as is accepted as the best available evidence of the position of the original corner.  
 NE corner of brick house S 20° W 89.99  
 NW corner of brick house S 55° W 132.24  
 SE corner of house foundation N 40° W 96.28  
 Dbl. hd. nail & disc in Tel. pole N 80° W 136.88  
 Iron pipe South 32.96

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-19-95

Signed by Glenn E. Richard Date Nov. 3, 1995  
 Glenn E. Richard

Surveyor's Michigan License No. 13040