

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LIBER 1 PAGE 145

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

3 DEC 96 3:20 P.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 6-S R 4-E L-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on October 3 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher Set 1/4 Sec. post B.Oak 12 S 55 W 14, B. Oak 11 S 15 E 56. Couldn't find any information on this corner in any of the old survey records. March 1973, We dug in line with old fence lines N. & S. and found large pointed stone. Set 3/4" X 24" iron pipe, replaced stone next to iron pipe and recorded it in L.2, P. 273.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 3, 1996 F.I.P. 12" deep at north edge of new pavement. Couldn't get the I.P. out. Set piece of ground rod in the F.I.P. & 3/4" X 3" gas pipe over the rod and drove them down. Set monument box & asphalted around the box. The center of the box is at the north edge of the pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E.R. 13040 over ground rod over iron pipe in monument box and is accepted as the best available evidence of the position of the original corner.
 "X" cut on East end C.M.P. N 85° W 183.02
 NE. corner of house (brick) N 30° W 163.74
 Found iron pipe "W.E.S." North 33.01
 Found iron pipe "G.E.R." South 33.00
 Re-mon tag in Elec. pole N 5° E 25.47
 Re-mon tag in 14" Walnut South 83.02



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-29-1996

Signed by Glenn E. Richard Date Nov 27, 1996
 Glenn E. Richard

Surveyor's Michigan License No. 13040