

OCT 21 1997

COMMISSION

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 6 - S R - 4 - E	L - 9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

9 OCT 97 3:38 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on June 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819 Joseph Fletcher D.S. set post B. Ash 10 S 87 W 17 Beech 6 N 7 E 39
Oct. 1841 Section 24 & May 1843 Section 25 were subdivided by S.C. Boughton, County Surveyor (monuments were not described)
J.L. Richard records from early 1900's called for stone.
S.W. corner of house N 50 E 100.8-End post N 30'
Oct. 1970 I dug through the pavement and found stone & cedar stake. Raised with iron pipe
S.W. corner of house foundation N 55 E 100.88 - 20" Walnut S 10 E 99.45
Sept. 1972 K.L. Suydam found the iron pipe and recorded it in L 2, P 147.
June 1993 Road under reconstruction. Found bottom of IP which checked remaining witnesses. Set 3/4" X 2.3 iron pipe in base course of asphalt. Cut off 0.7 of iron pipe as it hit the stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 20, 1997 I found the iron pipe as set on June 1, 1993 under the final coat of asphalt and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 2.3 iron pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
SW corner of house foundation N 65° E 100.81
NW corner of house foundation N 55° E 115.73
"X" cut on 15" CMP S 20° E 60.85
"X" cut on 15" CMP S 20° W 61.06
"X" cut on 30" CMP S 45° W 38.99
"X" cut on 30" CMP N 60° W 60.67
spike & disc in 20" Walnut S 10° E 99.45



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Sept 19, 1997
Glenn E. Richard

Surveyor's Michigan License No. 13040