

SURVEY & REMONUMENTATION

Filed under Remonumentation Act 345 of 1990

SEP 08 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 107

COMMISSION

For corners in

Lenawee Located In: _____ Corner Code # _____
(County)

- 1. Public Land Survey T 6 - S R 4 - E L 11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

FILED
AUG 08 1996
12:57 P.M.
LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 10 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set 1/4 post Lynn 16 N 77 W 14, Lynn 10 S 81 W 9
Oct. 1841 S.C. Boughton County surveyor subdivided Section 25, Town 6 South, Range 4 East but didn't describe any of the monumentation
May 3, 1882 James Blair "found stone"
Early 1900's J.L. Richard records call for stone
May 25, 1968 I dug but didn't find any stone. I set an iron pipe by extending line west and by doubling the distance measured between stones called for in J. Blair survey of 1885 at the Northeast corner of the Section and the NW corner of the NE 1/4, NE 1/4, Section 36

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 10, 1996 Found iron pipe as set in 1968. Removed and set 30" Harrison monument.

Note: The corner is 2' ± West of the west edge of the 5' C.M.P. which runs NW-SE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
Cut "X" on 5' C.M.P. S 55° E 20.67
Dbl. hd. nail & disc in east face of Elec. pole S 05° W 29.06
Cut "X" on 5' C.M.P. N 30° W 31.01
Dbl. hd. nail & Re-Mon tag in South face of electric meter pole N 85 E 305.42



Ratified by Peer Group in accordance with P.A. 345

Co. Rep. Glenn E. Richard Date 7-16-96

Signed by Glenn E. Richard
Glenn E. Richard

Date 7-27-96

Surveyor's Michigan License No. 13040