

MAY 16 1997

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1 PAGE 155

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T -6-S R -4-E Corner Code # M-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

17 DEC 96 9:19 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 3 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819, Joseph Fletcher set post cor. Sec. 12 & 13, Cypress 5. S 81 E 3, Cypress 4 S 17 W 11. Could not find any information on this corner in any of the old survey records. April 1973, We dug a trench across the road. This area is very unstable. We found remains of rotted out corduroy road, but nothing else. I set 3/4" X 4' iron pipe in center of road fences and on extension of irons found along line to south and recorded it in L. 2, P. 279.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 12, 1996, Found 3/4" X 2' galv. pipe bent over. It wasn't the one set by me and it didn't check the remaining witnesses or the re-rod set 6.60 South of my iron by K.L. Suydam for A-5, T6S-R5E in 1983. I re-traced surveys West and East and they fell 0.07 South and 0.29 West of the F.I.P. October 3, 1996, I set a 5/8" X 4' re-rod capped G.E.R. 13040 in Monument box at the location I had established in 1973.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 4' re-rod capped G.E.R. 13040 in monument box as is accepted as the best available evidence of the position of the original corner.
"X" on North end C.M.P. S 15° W 161.61
"X" on East end C.M.P. S 70° W 90.77
Dbl. hd. nail & re-mon tag in 28" Ash N 85° W 98.80
Dbl. hd. nail & re-mon tag in 10" Ash North 53.18
Found nail & disc in Elec. pole N 5° E 30.07
5/8" X 4' re-rod in monument box A-5, T6S-R5E, South 6.60



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-29-1996

Signed by Glenn E. Richard Date 12-6-96
Glenn E. Richard

Surveyor's Michigan License No. 13040