

MAY 16 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

3 DEC 96 3:20 P.M.

JEANNETTE D. KNOX  
REGISTER OF DEEDS

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 6-S R 5-E      A-5  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 3 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. August 1819, Joseph Fletcher intersect W. Bdy. 10 lks S. of post  
 Set post at intersection cor. Sec 7 & 18, Cypress 4 S 74 W 4, Cypress 5 N 22 E 10.  
 Could not find any information on this corner in any of the old survey records.  
 Nov. 1983, K.L. Suydam set 3/4" X 48" re-rod 6.6 South of Raisin Corner and recorded it in L. 5, P. 111.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 12, 1996, I found the re-rod 6.90 feet south of the iron pipe I found at M-5, T6S-R4E. We sighted to this corner in 1986 and it measured 6.63 to corner North. Retraced our 1986 survey and it fell 0.2 North of the found re-rod.  
 October 3, 1996, I set 5/8" X 4' re-rod capped G.E.R. in monument box on line between M-5 and 6, T6S-R4E, 6.60 South of M-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 4' re-rod capped G.E.R. in monument box and is accepted as the best available evidence of the position of the original corner.  
 "X" cut on North end C.M.P. S 15° W 155.18  
 "X" cut on East end C.M.P. S 75° W 88.92  
 Dbl. hd. nail & re-mon tag in 28" Ash N 80° W 99.69  
 Dbl. hd. nail & re-mon tag in 10" Ash North 59.76  
 Found nail & disc in Elec. pole N 05° E 36.64  
 5/8" X 4' re-rod in monument box M-5, T6S-R4E North 6.60



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-29-1996

Signed by Glenn E. Richard Date Nov 27, 1996  
 Glenn E. Richard

Surveyor's Michigan License No. 13040