

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

For corners in  
Lenawee  
(County)

Located In:

Corner Code #

1 AUG 97 3:31 P.M.

VICTORIA J. BOWTELL  
REGISTER OF DEEDS

1. Public Land Survey	T - 6 - S	R - 5 - E	A - 9
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on June 20, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819 Joseph Fletcher D.S. set post B Ash 4 N 70° W 8 N 24° E 9  
1853 S.C. Boughton subdivided section 30 "ancient or original corners all found by bearing trees"  
J. L. Richard records from early 1900' s called for stone. Corner post SW 32.2 and SE 39.4, end post N 30.2.  
10-9-40 Walter Frazier set a boat spike by using the above witnesses.  
March 12, 1984 I found the boat spike and recorded it in L 5 on P 97.  
5-28-93 The monument was destroyed about four years ago when the road commission started re-construction of the road.  
7-30-93 I set a 3/4" X 3' iron pipe in the base course of asphalt from remaining witnesses and by retracing of surveys that were tied to it before it was destroyed.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 20, 1997 I found the iron pipe as set on July 30, 1993 at S. edge of N 1/2 of final coat of asphalt. Set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. PS 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
Iron pipe North 33.00  
" X " cut on CMP N 65° E 49.43  
" X " cut on CMP S 25° E 35.22  
dbl hd nail & disc in E.P. S 40° W 36.11  
dbl hd nail & disc in guy pole N 30° W 34.44  
SE corner Sec 24, T6S R4E North 7.30

SURVEY &  
REMONUMENTATIO  
AUG 25 1997  
COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Nov. 18, 1993

Signed by Glenn E. Richard Date 6-26-97  
Glenn E. Richard

Surveyor's Michigan License No. 13040