

**SURVEY &
REMONUMENTATION**

SEP 03 1996

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee
(County)

Located In:

Corner Code #

1. Public Land Survey T-6-S R-5-E A-11
T-6-S R-4-E M-11
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

LIBER **001** PAGE **108**

FILED

AUG 08 1996

12:57 P.M.

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 10 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set post Corner Sec 25 and 36, Sugar 10 S S 88 E 4, Beech 9 S55 W 21. October 1841 S.C. Boughton County surveyor subdivided Section 25, Town 6 South, Range 4 East but didn't describe any of the monumentation
October 22, 1885, James Blair "found stone" Pine 4 N 47 E 84 1/2 (55.77)
Early 1900's J.L. Richard records call for stone
May 25, 1968, I dug and found stone and small iron pin on top and added iron pipe with top bent so the top of the iron is over the stone.
Per original GLO, this is a common corner to M-11, 6-4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 10, 1996 Found iron pipe as set in 1968 over stone. Had to break it to get it out. Found ring of stones underneath with void in middle. Removed stones and found bricks around the void (soft spot with remains of wood) Set 30" Harrison monument stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as a careful and faithful perpetuation of the position of the original corner.
Dbl. hd. nail & disc in South face 24" Pine N 47 E 56.10 (same tree as Blair's survey in 1885)
Dbl. hd. nail & disc in West face Elec. pole S 40 E 42.09
Dbl. hd. nail & Re-mon tag in West face E.P. N 10 E 161.32
Dbl. hd. nail & Re-mon tag in East face 24" Maple 78.70
"X" cut on E. end 5' C.M.P. S 50 E 28.20
"X" cut on W. end 5' C.M.P. S 45 W 26.12
"X" cut on N. end 3' C.M.P. N 50 W 53.78



Ratified by Peer Group in accordance with P.A. 345

Co. Rep. Glenn E. Richard Date 7-16-96

Signed by Glenn E. Richard Date 7-22-96
Glenn E. Richard

Surveyor's Michigan License No. 13040