

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T-6-S R-5-E	B-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

1 AUG 97 3:32 P.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on June 20, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5						3	2				
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	20	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Aug 1819 Joseph Fletcher D.S. set post B Ash 20 N 59° E 29 W. Oak 11 N 20° E 23, 1853 S.C. Boughton subdivided Section 30 "ancient or original corners all found by bearing trees"  
J. L. Richard records from early 1900's called for gas pipe with five small brick & tile, original stake 1 1/2 ft underneath. Concrete end post South 26'  
Jan 26, 1967 Werner Sommer found boat spike in the pavement.  
April 25, 1975 I found the boat spike and recorded it in L 3 on P 225.  
5-28-93 The monument was destroyed about four years ago when the road commission started re-construction of the road.  
6-4-93 Dug and found 2" sq. wood stake over iron pipe 12" deep. Set 3/4" X 3" iron pipe by driving down the original iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 20, 1997 I found the iron pipe under asphalt pavement. Set monument box level with final coat of asphalt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" iron pipe capped G.E.R. PS 13040 in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.  
dbl hd nail & disc in 16" Hickory N 75° E 101.57  
dbl hd nail & disc in T.P. N 80° W 136.59  
" X " cut on 12" CMP S 65° W 49.08  
" X " cut on 12" CMP S 5° W 21.56  
" X " cut on face of sq. conc post South 26.63  
NW corner of house foundation S 60° E 163.82  
NW corner of porch foundation S 65° E 161.81

SURVEY &  
REMONUMENTATION

AUG 25 1997

COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Nov. 18, 1993

Signed by Glenn E. Richard Date 6-26-97  
Glenn E. Richard

Surveyor's Michigan License No. 13040