

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE NUMBER 1 PAGE 180
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Lenawee Located in: Corner Code #
 (County)

1. Public Land Survey T-6-S R-5-E C-9
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R
 S T R

3. Miscellaneous S T R
 Property in Sec S T R

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED
 1 AUG 97 3:32 P.M.
 VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Aug 1819 Joseph Fletcher D.S. set post B Ash 10 N 10° E 5, B. Ash 10, S 13° W 14, 1853 S.C. Boughton subdivided Section 30 "ancient or original corners all found by bearing trees"
 J. L. Richard records from early 1900's called for stone S. pipe of E. hdwl NE 16.8 S. pipe of W hdwl NW 15.7
 April 15, 1975 I dug and found a 3/4" iron rod. The bridge had been replaced with a CMP. I recorded the corner on 4-25-75 in L 3 on P 223
 6-4-93 Found 3/4" X 18" iron rod lying flat in road under re-construction.
 Set 3/4" X 3' iron pipe from remaining witnesses which checked record distances to 1/4 corners South and West.

SURVEY & REMONUMENTATION

AUG 25 1997

COMMISSIONER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 20, 1997 I found the iron pipe as set on June 4, 1993 under new asphalt pavement (paved 6-19-97). Set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. PS 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 dbl hd nail & disc in Elec pole N 30° W 34.81
 NW corner of conc blk porch S 40° E 142.22
 NE corner of barn foundation S 30° W 137.15
 " X " cut on 24" CMP N 55° W 50.41
 " X " cut on 36" CMP N 25° W 30.47
 " X " cut on 36" CMP N 55° E 34.95



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Nov. 18, 1993

Signed by Glenn E. Richard Date 6-26-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040