

**SURVEY & REMONUMENTATION**

FEB 16 1999

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 286  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

**SECTION**

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 6 - S R - 5 - E	C - 10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property-Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10 DEC 1998 9:42:40 AM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Fletcher set 1/4 post Beech 12 N 47 E 20, Beech 18 N 61 E 22  
 Couldn't find any information on this corner prior to the survey of Blissfield Highway  
 1919 J.L. Richard survey of Blissfield Hwy. called for the corner, but didn't describe type of monumentation  
 1975 Roger Meinke & Tim Mohr, under my direction dug and found 3/4" iron rod next to stone & raised to the surface with 60d spike. I recorded it in L. 3, P. 223

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 16, 1998 Found 60d spike over 1" X 30" iron bar on the west side of a small (6" dia.) stone. Had to remove the stone to set a monument box. Replaced the 60d spike and 1" iron bar with 5/8" X 3' re-rod with Lenawee County Remon cap stamped P.S. 13040. The 1" iron bar was leaning South because there is another stone deeper. The bottom of the 5/8" re-rod also leans south with the top bent to be plumb.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with a Lenawee County Remon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner

- Fd. iron pipe 18" deep on 1/4 line West 33.00
- Set re-rod 12" deep on 1/4 line East 33.00
- Short steel fence post East 27.2
- C-9, T6S-R5E North 2649.69 (Len. Co. Re-mon corner)
- C-11, T6S-R5E South 2633.91 (Len. Co. Re-mon corner)



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 11-3-98

Signed by Glenn E. Richard Date Nov. 10, 1998  
 Glenn E. Richard

Surveyor's Michigan License No. 13040