

**SURVEY & REMONUMENTATION**

FEB 16 1999

SECTION

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 287  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

10 DEC 1998 9:43:02 AM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T - 6 - S R - 5 - E	C - 11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11		●											
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 1819 Joseph Fletcher set post cor. Sec. 29, 30, 31 & 32 Elm 10 S 51 W 12, W. Oak 30 N 72 E 9  
 Couldn't find any information on this corner prior to the survey of Blissfield Hwy.  
 1919 J.L. Richard survey of Blissfield Hwy. called for gas pipe.  
 1975 Roger Meinke & Tim Mohr, under my direction dug and found a gas pipe and raised to the surface with a 60d spike.  
 1985 I found a 60d spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 October 16, 1998 Found 60d spike in top of 1"X28" iron pipe. Found 1 1/2" square wood stake 12" deep and 1/2" iron rod 0.12 East and 0.08 North of 1" iron pipe. Replaced the 1" iron pipe with 5/8" X 3' re-rod with Lenawee County Remon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 5/8" X 3' re-rod with a Lenawee County Remon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner  
 "X" cut on 24" CMP N 45° W 30.55  
 "X" cut on 24" CMP N 45° E 30.61  
 "X" cut on 60" CMP S 55° E 35.69  
 "X" cut on 60" CMP S 55° W 35.22  
 Fd. dbl. hd. nail & disc in Elec. pole S 35° E 40.86  
 Fd. P.K. Nail in Elec. pole N 20° W 73.38



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 11-3-98  
 Signed by Glenn E. Richard Date Nov. 10, 1998  
 Glenn E. Richard  
 Surveyor's Michigan License No. 13040