

SURVEY & REMONUMENTATION

FEB 16 1999

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 288
 STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

SECTION _____

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>6-S</u> R <u>5-E</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10 DEC 1998 9:43:32 AM

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Fletcher set 1/4 Sec. post Beech 10 N 68 W 15, Sugar 10 N 20 W 21
 1880 James Blair found a stone
 1883 James Blair found corner
 1919 J.L. Richard surveyed Blissfield Hwy. Notes call for iron & stone
 1958 Ken Suydam found iron
 1976 Jack Gillin under the direction of Werner Sommer dug and found large iron 18" deep & raised with a 3/4" iron pipe recorded it in L. 3, P. 440

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 16, 1998 Found 1/2" X 12" iron pipe 4" deep over 1" X 2' iron bar (form pin) and RR spike tipped over. Probed for stone but didn't hit anything. Replaced all with 5/8" X 3' re-rod with Lenawee County Remon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with a Lenawee County Remon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner

NE corner of sandstone foundation of church S 40° W 99.98
 Dbl. hd. nail & Len. Co. remon tag in 36" Maple S 30° E 57.49
 "X" cut on CMP S 65° E 31.48
 "X" cut on CMP S 65° W 32.74



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 11-3-98

Signed by Glenn E. Richard Date Nov. 10, 1998
 Glenn E. Richard

Surveyor's Michigan License No. 13040