

**SURVEY &
REMONUMENTATION**

FEB 16 1999

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 289

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

Lenawee
(County)

Located In:

Corner Code #

10 DEC 1998 9:43:54 AM

- | | | | | |
|------------------------------------|---|------|-------|------|
| 1. Public Land Survey | T | -6-S | R-5-E | C-13 |
| | T | | R | |
| | T | | R | |
| | T | | R | |
| 2. Property Controlling in Section | S | T | R | |
| | S | T | R | |
| 3. Miscellaneous Property in Sec | S | T | R | |
| | S | T | R | |

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1815 Alexander Holmes, set post Cor. Sec.'s 31 & 32, Elm 9 N 45 E 6, Lynn 12 S 10 E 10
- 1880 James Blair found stake and stone
- 1883 James Blair found corner
- 1919 J.L. Richard surveyed Blissfield Hwy and called for the corner "stake" being 7' right (East) of center line
- 1954 Werner Sommer & I dug and found piece of cast iron and added "iron"
- 1973 I found iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 16, 1998 1/2" galv. pipe 6" deep on north side of piece of cast iron 14" deep which is on the north side of pointed stone 19" deep. Replaced the 1/2" galv pipe with 5/8" X 3' re-rod with Lenawee County Remon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with a Lenawee County Remon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner

- Fd. small round hd. spike in Elec. pole N 45° E 42.51
- Fd. small round hd. spike in Elec. pole West 38.72
- Cut "X" on CMP S 45° E 30.49
- Cut "X" on CMP S 50° W 34.51
- Stone at C-1, T7S-R5E West 21.55 with galv. pipe 0.5 W. of stone



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 11-3-98

Signed by Glenn E. Richard Date Nov. 10, 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040