

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE **1** **PAGE 181**
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Lenawee Located In: Corner Code #
(County)

1. Public Land Survey T-6-S R-5-E D-9
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec S T R

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED
 1 AUG 97 3:33 P.M.
 VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9		●											
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on June 20, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Aug 1819 Joseph Fletcher D.S. set post Lynn 20 S 1° E 21, Beech 12, S 59° E 26, Could not find any records about this corner other than the recording by Kenneth Suydam in L 4 on P 304. He states he found iron pipe 7-3-93 I found 3/4" X 18" old rusty bent galv. pipe lying flat 6" deep. The pavement was scarified about four years ago. Dug deeper and found spot in sub soil where the iron pipe had been and replaced the short pipe with 3/4" X 3' iron pipe. The witnesses on the recorded certificate don't fit.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 20, 1997 I found the iron pipe as set on July 3, 1993 12" deep under new asphalt pavement (paved 6-19-97). Raised and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped PS 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 dbl hd nail & disc in 24" Walnut S 80° W 187.53
 fd nail & disc in SW side of Tel pole N 45° W 39.65
 SW corner of garage foundation S 40° E 228.05
 1/2" re-bar on 1/4 line North 46.89
 FIP capped WEF 17636 North 5324.07



SURVEY & REMONUMENTATIO
AUG 25 1997
COMMISSION

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Nov. 18, 1993

Signed by Glenn E. Richard Date 6-26-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040