

**SURVEY &
REMONUMENTATION**

Filed under Remonumentation Act 345 of 1990

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

LIBER 001 PAGE 50

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - <u>6</u> - S R - <u>5</u> - E	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED 2:00 P.M.

DEC 05 1994

LENAWEE COUNTY
JEANETTE D. INOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. August 1819, Joseph Fletcher set 1/4 post, Maple 4 S 23 E 7, W. Ash 10 S 68 W 9
 J.L. Richard record from early 1900's show distances from the center and 1/8 corner in Section 20.
 December 8, 1977, K.L. Suydam doubled the distance between the occupied Center of Section 21 and the occupied 1/8 corner in Section 20 and set 1/2" X 14" iron pipe in line of end post on West side of road and recorded it in L.5, P.4, nail & shiner in Elec. pole N 30° W 82.25.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11-10-93, I found the iron pipe hit and bent. I re-traced the K.L. Suydam survey to re-set the iron and hit a stone. Dug and found pointed stone 14" deep, set 3/4" X 12" iron pipe over stone which checked the K.L. Suydam survey and witnesses.
 10-26-94, Removed the 14" iron pipe and set 3/4" X 3" iron pipe capped P.S. 13040 in monument box. I drove the iron pipe beside the stone and bent the top of it so as to be at the location of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" iron pipe capped P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.
 Cut "X" on C.M.P. N 50° W 23.28
 Cut "X" on C.M.P. N 55° E 24.27
 Dbl. hd. nail & disc. in Elec. pole N 30° W 80.83
 Fd. nail & disc. in Elec. pole (top cut off) N 30° W 82.25
 Face of 2 1/2" galv. post West 26.30



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 3, 1994

Signed by Glenn E. Richard Date Nov-11, 1994
 Glenn E. Richard

Surveyor's Michigan License No. 13040