

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE LIBER 1 PAGE 182
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

1 AUG 97 3:33 P.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

For corners in Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6-S</u> R <u>5-E</u>	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Glenn E. Richard, in a field survey on June 19, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Aug 1819 Joseph Fletcher D.S. set post Sycamore 16 S 30° W 14, B. Ash 10, N 73° E 8, J.L. Richard records from early 1900's called for stone and bricks. Lenawee County Road Commission scarified the pavement about four years ago and added limestone for roadway. June 17, 1994, Dug 12' X 12' X 2' deep with backhoe at intersection of roads. Found the bottom 6" of a 1 1/2" square wood stake and seven 1/2" to 1" pieces of brick over old remains of 3/4" X 1 1/2" wood stake. Set 3/4" X 3" gas pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 19, 1997 I found the iron pipe as set June 17, 1994 under base course of asphalt. Set monument box with top 1 1/2" above existing pavement for final course.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E.R. PS 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 " X " cut on CMP N 40° W 34.29
 " X " cut on CMP N 40° E 34.30
 SW corner of conc block bldg N 70°E 244.18
 dbl hd nail & disc in Elec pole S 45° W 44.14

**SURVEY &
 REMONUMENTATION
 COMMISSION**
 AUG 25 1997



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Sept. 24, 1994

Signed by Glenn E. Richard Date 6-26-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040