

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 48

For corners in

Lenawee  
(County)

Located In:

Corner Code #

1. Public Land Survey T - 6 - S R - 5 - E E - 10  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. August 1819, Joseph Fletcher set 1/4 post, B. Ash 12 N 30 E 6, Maple 6 S 39 E 9.  
 August 1881, James Blair found stake and set a new one.  
 January 1986, I found two C.M.P.'s under the road next to location of the corner. Set 5/8" X 24" iron rod in line with occupied line from West (center line of ditch east) by doubling the distance between the occupied Center of Sec. 29 and the occupied 1/8 corner and record distance from the N-S 1/4 line in Section 28 and recorded it in L.5, P.159 Cut "X" on C.M.P. N 45° W 26.55  
 Cut "X" on C.M.P. N 80° E 29.67

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 1994, Found 5/8" rod as recorded in L.5, P. 159  
 The James Blair survey of Section 28 doesn't show any distances North or South from this corner.  
 June 17, 1994, I dug with a back hoe at the N. 1/4 corner and found the N. 1/4 corner and computed the center of the section. My computed distance, from the computed Center of the Section, is 1.5 shorter than Blair 1881 distance.  
 October 24, 1994, Replaced the 5/8" rod with a 30" Harrison monument stamped P.S. 13040, and found no virgin stake due to the close proximity to the C.M.P.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.  
 Fd. "X" on C.M.P. N 30° W 26.59  
 Fd. "X" on C.M.P. N 85° E 29.73  
 NE Cor. of brick house S 40° E 163.92  
 NW Cor. of brick house S 30° E 148.71  
 SW Cor. of brick house S 20° E 192.32  
 Corner is 2' East of West edge of gravel road  
 Corner is 6' North of the Center of the E.W. 48" C.M.P.

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 3, 1994

Signed by Glenn E. Richard Date Nov. 11, 1994  
 Glenn E. Richard

Surveyor's Michigan License No. 13040

**FILED**

DEC 05 1994 2:01 P.M.

LENAWEE COUNTY  
 JEANETTE D. Y'NOX  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

