

**SURVEY &  
REMONUMENTATION**

Filed under Remonumentation Act 345 of 1990

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 55

**COMMISSION**

For corners in

Lenawee  
(County)

Located In:

Corner Code #

- |                                    |           |           |               |
|------------------------------------|-----------|-----------|---------------|
| 1. Public Land Survey              | T - 6 - S | R - 5 - E | <u>E - 11</u> |
|                                    | T _____   | R _____   | _____         |
|                                    | T _____   | R _____   | _____         |
|                                    | T _____   | R _____   | _____         |
| 2. Property Controlling in Section | S _____   | T _____   | R _____       |
|                                    | S _____   | T _____   | R _____       |
| 3. Miscellaneous Property in Sec.  | S _____   | T _____   | R _____       |
|                                    | S _____   | T _____   | R _____       |

**FILED**

DEC 05 1994 2:01 P.M.

LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. August 1819, Joseph Fletcher set post Elm 6 S 7 E 3, W. Oak 10 N 69 E 3  
August 1881, James Blair found stake.  
September 11, 1973, W.E. Sommer dug with back hoe and found cedar stake 3' deep at south edge of road and set 3/4" iron and recorded it in L. 2, P. 499 P.K. nail and disc in Elec. Pole N 25° W 69.88  
P.K. nail & disc in Tel. Pole N 45° E 51.15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 25, 1994, Found 3/4" iron pipe.  
October 26, 1994, Removed the iron pipe and set 30" Harrison monument stamped P.S. 13040. Also found pieces of the cedar stake and small pieces of crockery about 2' deep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is the best available evidence of the position of the original corner.  
Fd. p.k. nail & disc in east face of elec. pole N 20° W 69.93  
Fd. p.k. nail & disc in west face of post next to tele. pedestal N 40° E 51.22  
Cut "X" on north end C.M.P. N 30° W 40.35  
Cut "X" on south end C.M.P. S 45° W 21.22  
North face of 4" steel post south 40.57



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 3, 1994

Signed by Glenn E. Richard Date Nov. 11, 1994  
Glenn E. Richard

Surveyor's Michigan License No. 13040