

SURVEY & REMONUMENTATION

SEP 03 1996

COMMISSION

Filed under Remonumentation Act 345 of 1990

LIBER 001 PAGE 101

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee
(County)

Located In:

Corner Code #

1. Public Land Survey T-6-S R-5-E E-13
 T_____ R_____ _____
 T_____ R_____ _____
 T_____ R_____ _____
2. Property Controlling S_____ T_____ R_____ _____
 in Section S_____ T_____ R_____ _____
3. Miscellaneous S_____ T_____ R_____ _____
 Property in Sec. S_____ T_____ R_____ _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815, Alex Holmes set post corner Sec. 32 and 33 Ash 6 N 60° E 4, Elm 18 S 87° W 10 Dec. 1884, James Blair did a survey in Section 4, T7S-R5E and shows the jog of 48 links West of the NW corner of Section 4. Couldn't find any surveys of anyone ever finding or re-establishing this corner until I did in 1973. I re-established the NW corner of Section 4, T7S-R5E using information of J.L. Richard's records in Section 5, T7S-R5E and set an iron pipe 48 links West for E-13, T6S-R5E and recorded it in L. 2, P. 343.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 1995, Found iron pipe 4" below surface of pavement. Didn't find anything else while digging to set monument box. Replaced F.I.P. with 3/4" X 3" gas pipe capped G.E.R. P.S. 13040 and set monument box over iron pipe. James Blair record East to F-13, T6S-R5E is 2644.95, measured 2644.41

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 "X" cut on South end C.M.P. S 70° W 57.42
 "X" cut on North end C.M.P. N 40° W 32.85
 "X" cut on North end C.M.P. N 15° W 31.34
 "X" cut on South end C.M.P. S 55° E 46.87
 Dbl. hd. nail & disc in 12" Cedar N 20° W 91.88
 Dbl. hd. nail & disc in Elec. pole S 30° W 20.43
 E-1, T7S-R5E (NW corner Section 4) East 31.68

FILED

11:37 AM

JUN - 4 1996

LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 12-18-95

Signed by Glenn E. Richard Date 1-15-96
 Glenn E. Richard

Surveyor's Michigan License No. 13040