

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1 PAGE 183

For corners in

Lenawee (County)

Located in:

Corner Code #

- 1. Public Land Survey T-6-S R-5-E F-9
2. Property Controlling in Section S-T-R
3. Miscellaneous Property in Sec S-T-R

STATE OF MICHIGAN LENAWEE COUNTY FILED

1 AUG 97 3:33 P.M.

VICTORIA J. DANIELS REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on June 20, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Aug 1819 Joseph Fletcher D.S. set post B. Ash 12 S 25° W 7, Maple 9, North 3, On a survey by James Blair done in August 1881 he states he found a stake and added bricks. Early 1900's, J.L. Richard records "Drove gas pipe over stake & bricks, 12" soft Maple SE 56.7, End post South 32.3, 6" Red Oak SW 86.6 August 25, 1925 Walter Frazier set new gas pipe from the above witnesses. Lenawee County Road Commission scarified the pavement in 1990 and added limestone for roadway. June 17, 1994, All witnesses and lines of occupation are gone. Dug 10' square hole with backhoe and found field tile on end over remains of and old wood stake three feet deep. Set 3/4" X 3' gas pipe in old wood stake and left the tile as found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 20, 1997 Found the iron pipe as set June 17, 1994 under asphalt road. Raised the F.I.P. and set monument box 1 1/2" above level of existing asphalt to be level with the final coat of asphalt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. PS 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- 1/2" re-rod on 1/4 line South 40.74
dbl. hd. nail & disc in E.P. S 30° E 342.70
dbl. hd. nail & disc in E.P. S 35° W 375.66
N.E. corner of concrete porch S 85° W 665.34

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Sept. 29, 1994

Signed by Glenn E. Richard Date 6-26-97 Glenn E. Richard

Surveyor's Michigan License No. 13040

Grid table with columns A-M and rows 1-13. Cell (9, G) contains a black dot.

SURVEY & REMONUMENTATI

AUG 25 1997

COMMISSION

