

APR 01 1996

LAND CORNER RECORDATION CERTIFICATE

LIBER 001 PAGE 89

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T-6-S R-5-E F-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 4 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815, Alex Holmes set 1/4 Section post Lynn 15 S 15 W 4, Ash 8 N 21 E 24 Sept. 1881, described the corner as a stone and did a survey in the N 1/2 of Section 33 Dec. 1884, James Blair did a survey in Section 4, T-7-S and mentions the corner but doesn't described the monument.
1910± records of J.L. Richard describe the corner as stake and stone
J.L. Richard surveyed the road. Didn't described the monument but noted P.O.E. 0.8 South of Section corner.
Nov. 1975, Dug and found old piece of channel iron and tile which checked record jog to N 1/4 corner, Section 4, T7S-R5E and recorded it in L. 3, P. 342

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 4, 1995, Found the channel iron and tile as recorded which checked the only remaining witnesses. Replaced it with a 30" Harrison Monument stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument labeled Quarter corner stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
Stop sign post N 20° W 34.18
Stop sign post S 45° E 74.71
Dbl. hd. nail & disc in wood post S. of tel. pedestal S 70° E 71.99
N 1/4 corner, Section 4, T7S-R5E East 45.10, Harrison Monument.
SE. corner, Section 33, T6S-R5E East 2644.16, Harrison Monument.
SW. corner, Section 33, T6S-R5E West 2644.41, Harrison Monument.

FILED
NOV 22 1995 11:52 AM
LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-19-95

Signed by Glenn E. Richard Date 11-20-95
Glenn E. Richard

Surveyor's Michigan License No. 13040

