

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE** LIBER 1 PAGE 184  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Lenawee Located In: Corner Code #  
(County)

1. Public Land Survey T-6-S R-5-E G-9  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec S T R

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

1 AUG 97 3:34 P.M.

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on June 24, 19 97  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. set post Elm 12 N 46° E 21, Elm 12, N 40° W 22, Aug 9, 1819 Joseph Fletcher D.S.  
 On a survey by James Blair done in August 1881 he states he found a stake.  
 On records of J.L. Richard dated August 1916 he describes the corner as stake and bricks and witnessed to  
 the rails of a bridge North of the corner, but it has been replaced with a CMP.  
 May 12, 1974 I dug through the pavement and found wood stake on top of bricks 2.5' deep and raised with  
 3/4" X 4' pipe and recorded it in L 3 on P 9.  
 7-30-93 Found the bottom of iron pipe. The road commission had scarified the pavement and broke off part  
 of it. Couldn't get the iron pipe out so set a 3/4" X 3' iron pipe on top of it and drove them both down.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 24, 1997 I found the iron pipe as set on July 30, 1993 under base course of new asphalt. Set monument  
 box with top level with final course of asphalt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped PS 13040 in monument box and is accepted as a careful and faithful perpetuation  
 of the position of the original corner.

- " X " cut on top of CMP N 60° W 42.46
- " X " cut on top of CMP N 60° E 44.38
- Dbl hd nail & disc NE side of Elec pole N 5° W 328.53
- SE corner of brick house N 80° W 480.56
- 1/2 " Re-rod on Section line South 42.87'



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Nov. 18, 1993  
 Signed by Glenn E. Richard Date 7-15-97  
 Glenn E. Richard  
 Surveyor's Michigan License No. 13040

**SURVEY &  
 REMONUMENTATI**  
 AUG 25 1997  
 COMMISSION