

**SURVEY & REMONUMENTATION**

SEP 03 1996

**COMMISSION**

Filed under Remonumentation Act 345 of 1990

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 101

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 6-S R 5-E      H-13  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**FILED**

JUL 16 1996

*12:34 p.m.*

LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on June 5 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815 Alex Holmes D.S. set 1/4 post Ash 9 S 37 W 7 Ash 12 N 27 E 15  
 1970 J.L. Richard "Found nothing drove stake as 1/4 post"  
 Nov 1969 K.L. Suydam used a post on the north side of the road and ran line to re-establish the center of of Section 34  
 Feb 1970 I set a R.R. spike on line between the Section corners East & West and in line with the post used by K.L. Suydam  
 May 1977 We found a wood stake at the N 1/4 corner of Section 3 T7S R5E and another wood stake 24.35 West  
 Feb 1987 W.E. Sommer set an iron pipe using the information from my 1970 survey and recorded it in Liber 5, Page 176

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct 1995 Found the wood stake set by J.L. Richard in 1907 3.57' east of corner I had established in 1970 and recorded by W.E.Sommer in Liber 5 Page 176. This location was rejected by the peer group in favor of the stake set by J.L. Richard in 1907. June 5, 1996 set 30" Harrison monument at location of the found wood stake set by J.L. Richard in 1907.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument labeled Quarter Section stamped P.S. 13040 and is the best available evidence of the position of the original corner.  
 Dbl. hd. nail & re-mon tag in 36" Ash N 85° W 225.99  
 Dbl. hd. nail & re-mon tag in 30" Oak N 10° W 20.36  
 Angle iron fence corner post S 80° W 162.64  
 N 1/4 corner Section 3, T7S R5E West 24.35



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 12-18-95

Signed by Glenn E. Richard Date 6-21-96  
 Glenn E. Richard

Surveyor's Michigan License No. 13040