

APR 01 1996  
 COMMISSION

Filed under Remonumentation Act 345 of 1990  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 80

For corners in  
Lenawee Located In: Corner Code #  
 (County)

1. Public Land Survey T-6-S R-5-E 1-13  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

FILED

NOV 22 1995 11:56 AM

LENAWEE COUNTY  
 JEANETTE D. KNOX  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 18 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815, Alex Holmes set post corner Section 34 and 35, W. Oak 24 N 68 E 34, Cherry 5 S 26 W 9  
 1907, J.L. Richard found old stake, drove stake and tile  
 1910, J.L. Richard found old tile.  
 August 1951, K.L. Suydam found tile, set iron, SE corner of house N 30E 134.3.  
 May 1972, I found the iron pipe nearly rusted away and replaced it and recorded it in Liber 1, Page 441, SE corner of house N 30° E 134.3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 18, 1995, Found the iron pipe and tile and replaced it with a 30" Harrison Monument stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.  
 SW. corner of house N 17° E 121.90  
 S.E corner of house N 30° E 133.88  
 SE. corner of house N 8° W 289.41  
 "X" cut on face of 4" galv. post S 30° E 28.47  
 SE. corner of garage N 40° E 169.00  
 I-1, T7S-R5E, East 13.86



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10 - 19 - 95  
 Signed by Glenn E. Richard Date 11-3-1995  
 Glenn E. Richard  
 Surveyor's Michigan License No. 13040