

**SURVEY &
REMONUMENTATION**

Filed under Remonumentation Act 345 of 1990

LIBER **001** PAGE **63**

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 6 - S R - 5 - E	J - 11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

DEC 29 1994

3:51 P.M.

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11										●			
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on December 2 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set 1/4 post W. Ash 10 S 60 W 12, B. Ash 6 S 61 E 7.
August 1881, James Blair survey "Found the corner" (no description).
September 1915, J.L. Richard on survey of the road called for "corner (no description) 3' South of road center line".
August 1971, Walter E. Frazier & Associates re-traced the Blair survey and set a 1/2" rod in the pavement.
September 1976, I found the "iron rod and recorded it in L. 3, P. 438.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

December 2, 1994, All witness from 1976 recording are gone. I dug through the existing pavement and found the 1/2" iron rod 8" deep in the original pavement. I removed the iron rod and dug through the original pavement and probed for stone but found nothing. The existing road is 3' above the surrounding fields and a new large C.M.P. runs diagonally across the road just west of the corner. Set 3/4" X 3' iron pipe, capped G.E.R., P.S. 13040 in a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe in monument box capped G.E.R., P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
"X" cut on North end of C.M.P. N 20° E 32.67
"X" cut on South end of C.M.P. S 50° W 28.88
"X" cut on West end of C.M.P. S 70° E 39.49
NE. corner of conc. found. of house S 70° W 215.25
The corner is in the center of the south lane of the road.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 22, 1994
Signed by Glenn E. Richard Date Dec. 23, 1994
Glenn E. Richard
Surveyor's Michigan License No. 13040