

SURVEY & REMONUMENTATION

Filed under Remonumentation Act 345 of 1990

LIBER **001** PAGE **103**

SEP 03 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T - <u>6</u> - S R - <u>5</u> - E	<u>J - 13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

JUN - 4 1996

11:37 AM

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 18 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815, Alex Holmes set 1/4 Section post Ash 5 N 61 E 18, Ash 12 S 76 W 17
 Couldn't find any old records about this corner.
 November 1960, I dug and found old wood stake and bricks and added a 5/8" X 3' re-rod.
 May 1972, I found the re-rod and recorded it in L. 1, P. 439.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 18, 1995, I found the 5/8" X 3' re-rod and replaced it with a 30" Harrison monument stamped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
 Dbl. hd. nail & disc in square post North 21.77
 Re-rod buried 12" deep on 1/4 line North 33.00
 Re-rod buried 12" deep on 1/4 line North 157.12
 SE. corner of Sec. 35, T6S- R5E (K-13) East 2629.58



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 12-18-95

Signed by Glenn E. Richard Date 1-15-96
 Glenn E. Richard

Surveyor's Michigan License No. 13040