

SURVEY & REMONUMENTATION

Filed under Remonumentation Act 345 of 1990

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **49**

COMMISSION

For corners in

Lenawee
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|------------------------------------------|----------------|
| 1. Public Land Survey | T <u>6</u> - S <u>5</u> - R <u>5</u> - E | <u>K-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>Seg. #1</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED

DEC 05 1994

2:01 P.M.

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 24 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. August 1819, Joseph Fletcher set 1/4 post in prairie, no timber for bearings.
J.L. Richard record from early 1900's "Found (no description) half way between section corners".
August 30, 1948, the notes of a survey by K.L. Suydam show corner found (no description).
November 7, 1974, I dug and found large pointed stone. Set 3/4" X 4' iron pipe and placed stone on north side of the iron pipe and recorded it in L.3, P. 23 Dbl. hd. nail & disc in Elec. pole N 20° E 124.20
Iron pipe West 33.0

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 24, 1994, Found 3/4" X 4' iron pipe between two stones North and South, I removed the iron pipe and chiseled off part of the side of each stone and set a 30" Harrison monument stamped P.S. 13040 between the stone and placed the broken pieces of the stones around the Harrison monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
Fd. dbl. hd. nail & disc in west face of Elec. pole N 15° E 124.21
Fd. iron pipe West 32.87
SE. Corner of conc. block foundation, house No. 3500, N 60° W 94.14
NE. Corner of conc. block foundation, house No. 3500, N 30° W 153.49



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 3, 1994
Signed by Glenn E. Richard Date Nov. 11, 1994
Surveyor's Michigan License No. 13040