

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE LIBER 1 PAGE 187
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Lenawee Located in: _____ Corner Code # _____
(County)

1. Public Land Survey T-6-S R-5-E K-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec S _____ T _____ R _____
 S _____ T _____ R _____

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

1 AUG 97 3:35 P.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	6	5	4	3	2							
5													
6	8	7	6	5	4	3	2						
7													
8	9	8	7	6	5	4	3	2	1				
9													
10	10	9	8	7	6	5	4	3	2	1			
11													
12	11	10	9	8	7	6	5	4	3	2	1		
13													

I, Glenn E. Richard, in a field survey on July 08, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. August 1819 Joseph Fletcher set 1/4 post in prairie, no timber for bearings.
 J. L. Richard records from early 1900's "Found (no description) half way between section corner's."
 August 30, 1948, the notes of a survey by K.L. Suydam show corner found (no description).
 November 7, 1974, I dug and found large pointed stone. Set 3/4" X 4' iron pipe and placed stone on north side of the iron pipe and recorded it in L. 3, P. 23 Dbl. hd. nail & disc in Elec. pole N 20° E 124.20 Iron pipe West 33.0
 October 24, 1994, Found 3/4" X 4' iron pipe between two stones North and South, I removed the iron pipe and chiseled off part of the side of each stone and set a 30" Harrison monument stamped P.S. 13040 between the stone and placed the broken pieces of the stones around the Harrison monument.
Found in L 1 P 49 under re-mon

**SURVEY &
 REMONUMENTATION
 COMMISSION**

AUG 25 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 08, 1997 Found remains of Harrison monument 2 1/2' deep broken and tipped. The corner was destroyed during construction of the approach to a new bridge 200' +/- north. Set 3/4" X 3' iron pipe capped G.E.R. 13040 in monument box from the previous recorded witnesses in L. 1, P. 49 Lenawee County Remonumentation Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box.

Fd. dbl. hd. nail & disc in west face of Elec. pole N 15° E 124.22
 Fd. iron pipe West 32.87
 SE corner of conc. block foundation, house No. 3500, N 60° W 94.14
 NE corner of conc. block foundation, house No. 3500, N 30° W 153.52



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Nov. 11, 1994
 Signed by Glenn E. Richard Date 7-15-97
 Surveyor's Michigan License No. 13040