

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE **1** PAGE **185**
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Lenawee Located In: Corner Code #
 (County)

1. Public Land Survey T-6-S R-5-E K-9
 T R
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec S T R

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED
 1 AUG 97 3:35 P.M.
 VICTORIA J. DANIELS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 23, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. Aug 1819 Joseph Fletcher D.S. "set post in plain bearing trees"
 This corner was found by James Blair in August 1881, but didn't describe it or witness it.
 Old record of J.L. Richard called for stake.
 August 30, 1948 Walter Frazier re-established the corner.
 October 31, 1973 Werner Sommer found a 4" boat spike (rec. as 1/2 Iron bar) and recorded it in L 2, P 535
 11-6-93 Set 3/4" X 3" iron pipe from remaining witnesses, retracing W.E. Sommer Surveys in Section 25 and found iron pipe 33' N and W, set by Walter Frazier on his 1948 survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 June 23, 1997 The iron pipe I set 11-6-93 was gone. Set 3/4" X 3" iron pipe capped G.E.R. 13040 in monument box from witnesses and by extending section line from iron pipe 33.00' South and 1/4 corner common to sections 25 and 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 3/4" X 3" gas pipe capped PS 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Dbl hd nail & disc in Elec pole N 45° E 41.69
 Fd old iron pipe N 45° W 46.63 (12" deep)
 " X " cut on top of conc hdwl N 20° E 28.61
 Iron pipe on section line South 33.00
 3/4" X 3" iron pipe capped G.E.R. in monument box 1/4 corner North 2670.86

**SURVEY &
 REMONUMENTATION**
 AUG 25 1997
 COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Nov. 18, 1993
 Signed by Glenn E. Richard Date 7-15-97
 Surveyor's Michigan License No. 13040