

**SURVEY &
REMONUMENTATION**

APR 28 1995

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

FILED

DEC 29 1994

3:51 PM

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

| | | |
|-------------------------|-----------------------------------|---------------|
| <u>Lenawee</u> | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T - <u>6</u> - S R - <u>5</u> - E | <u>K-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling | S _____ T _____ R _____ | _____ |
| in Section | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ T _____ R _____ | _____ |
| Property in Sec. | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on December 2 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set post Sec. 35 & 36, Lynn 9 S 42 E 23, Elm 8 N 27 W 24. Found no record of this corner ever being found or used prior to July 1980. July 1980, We dug 12'± Easterly (no occupation) from the Northeast corner of Section 2, T7S-R5E, which I had found in December 1966 and an 80 year old land owner told me that the SE. corner of Section 35 was 12 ± East. We found a small piece of strap iron driven in the bottom of a wood stake, pieces of brick and two small stones, and set 1/2" iron pipe.
W.E. Sommer, R.L.S. No. 12030, recorded it in L. 4, P. 347. NE. cor. of garage S 10° W 130.58
NW. cor. of porch S 60° W 90.20
NE. cor. of porch S 50° W 74.0
NE. cor. of house S 30° W 100.04

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

December 2, 1994, I dug and found the 1/2" iron pipe. Removed the iron pipe and dug hole to set Harrison monument finding the two stones, strap iron and traces of wood stake. Set 30" Harrison monument stamped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
NE. corner of Section 2, T7S-R5E, West 11.23
NE. Cor. garage S 10° W 130.52
NW. Cor. porch S 60° W 90.25 (Aluminum siding)
NE. Cor. porch S 50° W 74.00 (Aluminum siding)
NE. Cor. house S 30° W 100.04



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 22, 1994
Signed by Glenn E. Richard Date Dec. 23, 1994
Glenn E. Richard

Surveyor's Michigan License No. 13040