

Filed under Remonumentation Act 345 of 1990 LIBER 1 PAGE 186
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 LEWIS & CLARK COUNTY
 FILED

1 AUG 97 3:35 P.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

For corners in
Lenawee Located In: Corner Code #
 (County)

1. Public Land Survey T-6-S R-5-E L-9
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec S T R
 S T R

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 24, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Aug 1819 Joseph Fletcher D.S. "set post in plain, no bearing trees,"
 J.L. Richard records from early 1900's called for iron bar.
 Walter Frazier found the iron bar in 1942.
 October 31, 1973 Werner Sommer found the iron bar and recorded it in L 2, P 535.
 The corner is 13' East of the road intersection.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 24, 1997 I found iron bars, bricks and sandstone.
 I had to split the sandstone in order to set the Harrison monument and placed the pieces of stone and bricks around it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.

Dbl hd nail & disc in 24" Maple N 10° E 105.16
 Dbl hd nail & disc in Elec pole S 40° E 28.18
 Dbl hd nail & disc in Elec pole S 5° E 334.89
 Survey mark spike & re-mon tag in Elec pole S 75° W 74.66

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**SURVEY &
 REMONUMENTATION**
 AUG 25 1997
COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date Nov. 18, 1993

Signed by Glenn E. Richard Date 7-15-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040