

7/17/95

Filed under Remonumentation Act 345 of 1990

LIBER 001 PAGE 79

LAND CORNER RECORDATION CERTIFICATE

APR 01 1996

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T - 7 - S R - 2 - E	<u>1-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

NOV 22 1995

11:52 AM

LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 23 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C.L.O. April 1824, John Mullet set 1/4 section post in stream Maple 5 S 4 W 77, Blue Beech 6 N4 E 59  
 June 14, 1972, I set 1" X 2' iron pipe by proportioning occupied lines both North and South and by extending fence line South from the North which is also in line with the center line of the bridge deck. Recorded same in Liber 2, Page 205.  
 July 1993, Found iron pipe. SW. corner bridge abutment S 60° W 16.48,  
 SE. corner of bridge abutment S 60° E 16.50

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 23, 1995, Found iron pipe under 7" of Asphalt. Removed it and set 3/4" X 3' gas pipe, capped G.E.R. P.S. 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R., P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
 Dbl. hd. nail & disc in NW. root 18" Maple S 85° E 109.45  
 Dbl. hd. nail & disc in W. face 18" Dbl. Oak S 5° E 128.45  
 SW. Cor. of bridge abutment S 60° W 16.48  
 SE. Cor. of bridge abutment S 60° E 16.50  
 SW. Cor. of SW. wing wall S 15° E 36.87  
 SE. Cor. of SE. wing wall S 15° E 36.85  
 N. edge of bridge deck South 7' ±  
 Centerline of Gorman Road pavement North 40' ±



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-19-95  
 Signed by Glenn E. Richard Date 11-20-95  
 Surveyor's Michigan License No. 13040