

MAY 16 1997

COMMISSIONER

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 118

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T - 7-S R - 2-E M-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

13 NOV 96 9:04 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on October 18 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1824, John Mullett set post cor. Sec. 12 & 13 W. Ash 7 S 15 W 38, W. Ash 6 N 18 W 33
Couldn't find any information on this corner in any of the old survey records.
1974 K.L. Suydam established A-5, T7S-R3E, 79 links (52.14) North from SE. corner of Section 12, Dover Twp.
1975 We sighted from the West to a found RR. spike 52.14 South from an iron pipe recorded for A-5, T7S-R3E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 1, 1996, The intersection had been reconstructed by the Lenawee County Road Commission . I dug and found a 1/2" X 16" re-bar capped W.E.F. 17636. Dug farther but didn't find anything else.
October 18, 1996, I set a 30" Harrison monument stamped P.S. 13040 at the locaton of the re-bar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
Dbl. head nail & re-mon tag in Elec. pole S 10° W 123.70
Dbl. head nail & re-mon tag in guy pole N 20° W 95.54
Dbl. head nail & re-mon tag in 30" Ash N 15° W 149.87
Dbl. head nail & re-mon tag in Elec. pole N 15° E 91.04
Found dbl. head nail & disc in Tel. pole S 40° E 18.91
3/4" gas pipe in monument box at A-5, T7S-R3E, North 52.18



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 8, 1996

Signed by Glenn E. Richard Date 10-29-96
Glenn E. Richard

Surveyor's Michigan License No. 13040