

**SURVEY &
REMONUMENTATION**

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **119**

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T - <u>7-S</u> R - <u>3-E</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec	S _____ T _____ R _____	_____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED
13 NOV 96 9:04 A.M.
JEANETTE D. KNOX
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 18 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1824, John Mullett Intersect W. bdy 79 L N of post Set post at intersection cor. Sec. 7 & 18, Beech 12 N 83 E 11, Whitewood 6 S 10 E 28
 Couldn't find any information on this corner in any of the old survey records.
 1974, K.L. Suydam "set a 1/2" iron pipe, North the record jog of 52.14 feet from the SE. cor of Sec. 12, Dover Twp. " and recorded it in L. 4, P. 242 in April 1979.
 January 1979, I found the iron pipe and recorded it in L. 4, P. 197.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 1, 1996, The intersection had been reconstructed by the Lenawee County Road Commission. All former witnesses are gone. Found 1/2" galv. pipe 12" deep, dug further but didn't find anything else. Set 3/4" X 3' gas pipe on town line 0.24 East of the found iron pipe.
 October 18, 1996, set monument box in new asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. in monument box and is accepted as the best available evidence of the position of the original corner.
 Dbl. hd. nail & re-mon tag in Elec. pole S 5° W 175.54
 Dbl. hd. nail & re-mon tag in guy pole N 45° W 51.33
 Dbl. hd. nail & re-mon tag in 30" Ash N 20° W 99.62
 Dbl. hd. nail & re-mon tag in Elec. pole N 40° E 44.02
 Harrison monument at M-5, T7S-R2E South 52.18



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 8, 1996

Signed by Glenn E. Richard Date 10-29-96
 Glenn E. Richard

Surveyor's Michigan License No. 13040