

**SURVEY & REMONUMENTATION**

OCT 19 1998

Filed under Remonumentation Act 345 of 1990. IBER 1  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

PAGE **278**  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

**SECTION**

25 SEP 1998 1:12:25 PM

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 7 - S R - 3 - E	C - 10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on July 1, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1824 John Mullett set 1/4 Sec. post Beech 18 S 84 E 16 Beech 9 N 53 W 20  
 Early 1900's J.L. Richards record. Iron under bricks 8" Walnut S 32 1/2 W 63 lks (41.58")  
 Oct. 1910 J.L. Richard Found iron and bricks  
 1916 J.L. Richard surveyed Sand Creek Hwy. & found iron & bricks  
 1949 Kenneth Suydam placed a reference of "Found" on the same page of J.L. Richards early 1900's record of the corner. He believes the "Found" is referring to J.L. Richards record as to type of monumentation and gives witness to the Walnut (stump) of 41.3  
 1971 W.E. Sommer found 1/2" iron pipe & recorded in L1 P39  
 1997 I found 60d spike in pavement which checked the witnesses taken by W.E. Sommer in 1971  
 1997 Lenawee County Road Commission rebuilt the road with the paving to be done in 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 1, 1998 Found 60d spike in top of iron pipe 12" under base course of asphalt. Replaced iron pipe with 5/8" X 3' re-rod with re-mon cap P.S. 13040 and set monument box. Drove the re-rod through bricks 20" deep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with re-mon cap P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner

Re-rod in concrete North 32.98  
 Re-rod North 66.89  
 dbl. hd. nail & re-mon tag in post S 65° W 77.16  
 Fd. dbl. hd. nail & disc in 16" Maple (stump) N 65° W 59.27  
 Fd. dbl. hd. nail & disc in E.P. N 15° W 29.97  
 Survey mark spike & re-mon tag in E.P. S 10° E 200.84



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 22, 1998

Signed by Glenn E. Richard Date Sept 23, 1998  
 Glenn E. Richard

Surveyor's Michigan License No. 13040