

SURVEY & REMONUMENTATION

OCT 19 1998

Filed under Remonumentation Act 345 of 1990 LIBER 1 PAGE 279
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

25 SEP 1998 1:13:20 PM

For corners in SECTION

Form with columns: Lenawee (County), Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on July 16, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at row 11, column B.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1824 John Mullett set post cor. Sec. 29, 30, 31, & 32 Butternut 12 S 70 E 31 Elm 10 N 75 W 53
Oct 1910 J.L. Richard found iron shaft under bridge
Early 1900's J.L. Richard record "stake under auger hole in bridge in S. edge of creek"
1949 W.E. Frazier set concrete nail & washer in bridge deck
1962 Kenneth Suydam found iron shaft on south river bank under bridge
1963 Kenneth Suydam set concrete nail & washer in concrete deck of new bridge by retracing the 1962 survey
1967 I found P.K. nail and washer in the bridge deck
1971 W.E. Sommer found concrete nail & washer in bridge deck and recorded it in L 1 P 37
1997 I found the P.K. nail in the bridge deck which checked the witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 16, 1998 I found the P.K. nail in custom built monument box installed by the Lenawee County Road Commission while paving Sand Creek Hwy. on July 2, 1998. I tried to get permission to set a more substantial monument but the road commission did not want me to drill into the bridge deck.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

P.K. nail in bridge deck in monument box and is accepted as the best available evidence of the position of the original corner.

Cut "X" on top of bolt on S. side of North guard rail post N 40° W 14.20
Cut "X" on top of bolt on S. side of North guard rail post N 40° E 31.13
Cut "X" on top of bolt on N. side of seventh from N. guard rail post S 20° W 29.30
Cut "X" on top of bolt N. side of seventh from N. guard rail post S 60° E 24.77
Face of concrete curb West 8.93
Face of concrete curb East 19.13



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 22, 1998

Signed by Glenn E. Richard Date

Surveyor's Michigan License No. 13040