

MAY 16 1997

Filed under Remonumentation Act 345 of 1990

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 140

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

2 DEC 96 9:03 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7-S R 3-E E-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on May 8 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 John Mullet D.S. set post corner Sec. 4, 5, 8 & 9 Maple 18 S 15 W 49, Lynn 14 N 16 W 14
Early 1900 records of J.L. Richard call for stone in center of present road.
March 1929, survey for M-34 by MSHD found stone with X and set spike over.
1959 Plat of Hickory Lane, recorded in Liber 14 of Plats, Page 41, is described from this corner.
March 1973, W.E. Sommer used center of monument box and recorded it in L. 2, P. 349

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 8, 1996, Used the three remaining witnesses and dug through 6" of asphalt and found the monument box. Found the stone and bricks over 2' deep. Couldn't find the cross so used center of the stone which is also the center of the monument box.
Raised the box to the surface by using two adjusting rings.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 24" gas pipe capped G.E.R. over stone in monument box and is accepted as the best available evidence of the position of the original corner.
Fd. dbl. hd. nail & disc in Guy pole S 20° E 52.70
Dbl. hd. nail & disc in Elec. pole S 25° W 53.71
Fd. dbl. hd. nail & disc in 18" Cedar S 75° W 106.54
Fd. dbl. hd. nail & disc in Elec. pole N 25° W 77.84
SW. corner of brick building N 60° E 216.27



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-29-1996

Signed by Glenn E. Richard Date Nov. 27, 1996
Glenn E. Richard

Surveyor's Michigan License No. 13040