

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 Filed

20 DEC 96 10:53 A.M.

JEANETTE D. KNOX  
 REGISTER OF DEEDS

For corners in Lenawee Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T - 7-S R - 3-E F-5  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 24 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John Mullett set 1/4 Sec. post B. Oak 18 N 19 E 30, B. Oak 5 S 25 E 11  
 Early 1900's, J.L. Richard record called for Iron, bricks, lime & stones  
 Dec. 1945, E. Alder (W.E. Frazier employee) Found iron, bricks, & stone and raised with boat spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 24, 1996, found boat spike in pavement over another boat spike which was over a piece of iron rail 18" deep on the north side of a stone surrounded by bricks & lime. Replaced the iron rail with a 3/4" X 3" gas pipe capped G.E. R. and set monument box with top 2 3/4" above pavement surface as the road commission will be paving on the 25th.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.  
 "X" on face of chain link fence end post S 70° W 85.63  
 "X" on face of chain link fence gate post S 35° E 31.83  
 Dbl. hd. nail & re-mon tag in Elec. pole North 30.38  
 Dbl. hd. nail & remon tag in Elec. poie S 10° W 73.49  
 NW. corner of concrete block bldg. S 5° E 75.52  
 NE. corner of concrete block bldg. S 40° E 155.34  
 NE. corner metal bldg. S 50° W 115.99



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 12-16-1996

Signed by Glenn E. Richard Date 12-18-96  
 Glenn E. Richard

Surveyor's Michigan License No. 13040