

JAN 2 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 388

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7-S</u> R <u>3-E</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

14 DEC 1999 4:32:57 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Glenn E. Richard, in a field survey on November 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1824 John Mullett set 1/4 Sec. post B. Oak 16 N 73 W 18 W. Oak 8 N 80 E 41
 Couldn't find any information on this corner before 1957
 1947 Walter Frazier did a survey in Section 15 but did not find or re-establish it
 1956 Werner Sommer shows corner on survey notes but not type of monumentation
 1957 MDOT records call for 1 1/4" iron pipe
 1961 I found 1 1/4" iron pipe and raised with spike
 1969 The corner was removed during bridge construction in May 1969. I set a iron pipe by retracing the information shown on MDOT's plans which checked the one remaining witness SW corner of house N 45 E 83.15
 Sept. 27, 1974 I found 1" iron pipe and recorded it in Liber 3 Page 3 SE bolt of guard rail N 80 W 53.72
 NE bolt of guard rail S 80 W 55.20
 Nov. 4, 1974 & 1980 Kenneth Suydam found iron pipe in monument box
 1992 Kenneth Suydam found iron pipe in pavement
 1997 Michael Bartolo found 1" iron pipe in monument box. Fd P.K. nail in E.P. North 32.03 Set nail & shiner in E. Face of E.P. S 30° E 72.30

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 19, 1999 Found 3/4" X 30" iron pipe under base course of asphalt. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and raised box with adjusting ring.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with re-mon cap P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner

Replaced nail & disc with dbl. hd. nail & re-mon tag in E.P. S 35° E 72.27
 Cut "X" on top of S.E. bolt of bridge guard rail N 75° W 53.70
 Cut "X" on top of N.E. bolt of bridge guard rail S 70° W 55.21
 Fd. P.K. in W. face of E.P. North 32.01



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 7, 1999

Signed by Glenn E. Richard Date Dec. 8, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040