

**SURVEY & REMONUMENTATION**

**OCT 19 1998**

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 276  
 STATE OF MICHIGAN  
 LENAWEЕ COUNTY  
 FILED

25 SEP 1998 1:11:44 PM

For corners in **SECTION**

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 7 - S R - 3 - E	H - 9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on August 27, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9				●									
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO John Mullett set 1/4 Sec. post B. Oak 10 N 48 E 32 B. Oak 12 S 54 W 45  
 1910 J.L. Richard found stone. W. Oak 20 N 12 1/2 E 51 links (33.66")  
 1955± MDOT witnesses 1/2" iron pipe N 16 E 34.00 34" Oak  
 1957 I found iron pipe and a bolt 183.25 East and 1.15 South in line with fence north.  
 J.L. Richard's 1910 survey called for fence north 2.76 chains (182.16") east of the corner.  
 1959 I found iron pipe  
 1972 I found iron pipe under the pavement & raised with 3/4" iron pipe and recorded it in L 2 P 199.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 9, 1998 I found 1/2" X 21" pinched bottom iron pipe under 3/4" iron pipe  
 July 15, 1998 I dug 1' east & 1' south of the F.I.P. and found a 8" X 6" X 4" stone lying flat. Found nothing under it. Because of how it was laying I think it may have been moved when road was graded years ago. It was 2' deep with top 2" in the gravel and the 2" in the sub soil. The centerline of the top surface was 1± E and 0.7± south of the F.I.P.. Replaced the F.I.P. with a 5/8" X 3' re-rod. The centerline of a 36" Oak stump is N 13° E 33.6 ±.  
 August 27, 1998 Set monument box in new asphalt pavement and placed Lenawee County re-mon cap on the 5/8" X 3' re-rod

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with re-mon cap stamped P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner

Survey mark spike & re-mon tag in E.P. N 10 E 53.13  
 dbl hd nail & re-mon tag in 12" Hickory South 25.14  
 dbl hd nail & re-mon tag in E.P. S 80° W 117.05  
 S.E. corner of house foundation N 35° W 112.82  
 S.W. corner of house foundation N 50° W 133.37  
 N.E. corner of house foundation (stone) S 40° W 104.95



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 21, 1998

Signed by Glenn E. Richard Date Sept. 14, 1998  
 Glenn E. Richard

Surveyor's Michigan License No. 13040