

SURVEY & REMONUMENTATION

OCT 19 1998

Filed under Remonumentation Act 345 of 1990 LIBER 1
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 284
 STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

SECTION

25 SEP 1998 1:15:18 PM

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 7 - S R - 3 - E	I - 3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 20, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1824 John Mullett set post on Sec. 2, 3, 10 & 11 W. Oak 14" S 65 E 16 W. Oak 12 N 55 W 30
- Early 1900's J.L. Richard's record Iron & bricks on top of stone
- 1925 Beecher Road survey called for "R.R. spike=Section corner"
- 1940± Walter Fraizer set a monument box when the concrete pavement was put in
- 1974 Iron pipe in monument box recorded by MDOT in L 2 P 621
- 1981 I found a iron pipe over stone in a monument box & recorded it in L 5 P 40
- 1997 Donald Bendzinski P.S. 35989 found iron pipe in monument box and recorded it in L 5 P 336

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 20, 1998 Found iron pipe (almost rusted away) in concrete in a monument box. Dug out some of the concrete & the iron pipe broke off. Drilled thru the remains of the iron pipe. Hit the stone when driving the re-rod and the rod tipped to the S.W. while driving it down. Bent the top 8"± to be plumb at the location of the found iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.

- "X" cut on south face of steel stop light pole N 20° W 35.18
- "X" cut on north face of steel stop light pole S 30° W 51.82
- "X" cut on NW bolt in base of AMOCO sign S 65° W 109.84
- "X" cut on south bolt in base of flood light pole N 75° W 113.47



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 22, 1998

Signed by Glenn E. Richard Date Sept. 23, 1998
 Glenn E. Richard

Surveyor's Michigan License No. 13040