

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000

**LIBER 1 PAGE 361**  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED  
 15 NOV 1999 9:56:22 AM  
 VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in **SECTION**  
Lenawee (County) Located In: Corner Code #

1. Public Land Survey T-7-S R-3-E I-10  
 T R  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec S T R

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO John Mullett set 1/4 Sec. post W. Oak 16 N 68 E 42 Hickory 7 N 63 W 108  
 Couldn't find any information prior to the 1916 road survey  
 1916 J. L. Richard surveyed the road "1/4 post in Sec.'s 26 & 27 Not found. Drove gas pipe & put bricks."  
 1956 MDOT survey of M-52 describe the corner as 1 1/4" iron pipe SE corner of house N 60 W 117.45  
 1971 Kenneth Suydam "Found 1" solid iron rod in box" and recorded it in Liber 1, Page 287  
 1975 Kenneth Suydam found 1" solid iron rod in box  
 1997 & 1998 I found 1" iron rod at bottom of broken monument box.  
 1998 Mike Bartolo found the monument box had been dug out during patching of the pavement

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

September 2, 1999 I retraced my 1988 survey and cut a "X" in the concrete pavement  
 September 9, 1999 Keith Schultz from MDOT with his crew and myself worked with another MDOT crew that bored through the concrete pavement. We found a 1" solid iron rod under the pavement directly under the "X" I had cut. We replaced the found rod (curb & gutter form pin) with a 5/8" X 3' re-rod and set a monument box.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

- Cut "X" on top of concrete R.O.W. post East 75.00
- Cut "X" on top of concrete R.O.W. post West 74.47
- NW corner of House #5474 foundation N 50° W 130.76
- Fd. dbl hd nail & disc in E.P. N N 30 W 149.97
- Cut "X" on S. end concrete drive culvert N 20 W 100.97

The corner is 1.74 west of survey centerline



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 26, 1999  
 Signed by Glenn E. Richard Date Oct. 29, 1999  
 Glenn E. Richard  
 Surveyor's Michigan License No. 13040