

DEC 22 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 310
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

16 DEC 1998 4:21:35 PM

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 7-S R - 3 - E	L-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Glenn E. Richard, in a field survey on December 12, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824 John Mullett set 1/4 post W. Oak 18 S 11 W 51, W. Oak 12 N 56 E 52
- 1876 Burton Kent "Found stone, one witness tree still standing"
- 1900 James Blair "Found iron bar under a large stone and bricks 18" Hickory S 2 1/8° W 80 lks (52.80")
- 1925 MSHD Survey called for "X" on stone 15" Hickory S 3° W 52.4
- 1939 Consumers Power Co. survey "Found 1/4" Timber spike
- 1972 Werner Sommer found iron rod in monument box and recorded it in L. 2, P. 77
- 1974 I found 1" iron rod in monument box.
- 1974 Kenneth Suydam found iron rod in monument box
- 1984 I found 1" iron rod in monument box.
- 1993 David Erickson P.S. 29245 "1" rod in monument box" and he found it again 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 12, 1998 Found 1" X 2' iron rod in monument box. Replaced it with a 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- SE cor of block bldg N 05° E 93.93
- SE cor of brick bldg N 30° W 73.99
- Fd dbl hd nail & DEE cap in T.P. N 55° E 40.07
- Fd dbl hd nail & DEE cap in E.P. S 20° W 21.85
- Fd "X" on N. face of E. gate post S 60° E 67.40



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 1, 1998

Signed by Glenn E. Richard Date Dec. 14, 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040