

REMONUMENTATION

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE LIBER 1 PAGE 158

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T-7-S R-3-E M-2
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec S T R

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

17 DEC 96 9:19 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 31 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Joseph Fletcher set qr. sec. post Hick. 12 S 45 W, W. Ash 10 S 58 W 46
James Blair records show B. Kent surveyed NE 1/4 & SE 1/4, Sec. 1 in 1876. B. Kent record calls for M-2 being 4 chains South of M-13, T6S-R3E (Type of monumentation not noted).
1907, J.L. Richard records "Drove gas pipe".
May 1933, Walter E. Frazier "Found iron & stones".
1941, Harold Clegg (W.E.F. employee) "Found iron".
Dec. 1953, K.L. Suydam (W.E.F. employee) located a point from wit. & dip needle.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 25, 1996, I dug and found a P.K. nail over boat spike 9" deep over stones, over 5/8" Sq. iron bar 2' deep and 0.23 West of line between M-1 and M-3, T7S-R3E.
Set 3/4" X 3' gas pipe, capped G.E.R. 13040, 0.23 East of found iron.
October 31, 1996, I set a monument box over the gas pipe I set on 9-25-96 and moved the iron pipe over 0.01 East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.
Dbl. hd. nail & re-mon tag in 16" Walnut N 55° W 30.27
Dbl. hd. nail & re-mon tag in 18" Walnut N 20° W 64.89
Dbl. hd. nail & re-mon tag in Elec. pole N 15° E 97.97
Dbl. hd. nail & re-mon tag in Elec. pole S 20° E 79.48
Fd. nail & shiner in Elec. pole S 35° W 26.82
3/4" X 3' gas pipe in monument box at M-1, T7S-R3E North 263.10
3/4" X 3' gas pipe in monument box at A-2, T7S-R4E North 14.52



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-08-1996

Signed by Glenn E. Richard Date 12-11-96
Glenn E. Richard

Surveyor's Michigan License No. 13040

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993