

JAN 12 5 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 380  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

SECTION

For corners in Lenawee (County) Located In: Corner Code #

1. Public Land Survey T-7-S R-4-E C-12  
T R  
T R  
T R

2. Property Controlling in Section S T R  
S T R

3. Miscellaneous Property in Sec S T R  
S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

7 DEC 1999 1:04:44 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Glenn E. Richard, in a field survey on October 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Fletcher set 1/4 Sec. post Elm 8 N 50 E 0 Elm 15 N 70 W 18  
1888 & 1891 James Blair described the corner as stake in tile and brick below  
Early 1900's J. L. Richard's record is the same as Blair's  
1920 J.L. Richard surveyed Hodges Hwy. "Found stake and glazed tile & drove gas pipe"  
1975 I dug and found glazed tile, bricks and iron pipe. I raised to the surface with a 3/4" X 4' iron pipe and recorded it in Liber 3, Page 221.  
1996 Steve Young found iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 9, 1999 Found 1" X 4' iron pipe under new asphalt pavement. Replaced pipe with 5/8" x 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Survey mark spike and re-mon tag in E.P. N 60° E 59.56  
"X" cut on CMP S 50° E 38.95  
"X" cut on CMP S 55° W 37.64  
"X" cut on CMP N 25° W 41.51



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999  
Signed by Glenn E. Richard Date Dec. 4, 1999  
Surveyor's Michigan License No. 13040