

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 381
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T -7- S R -4- E	D-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

7 DEC 1999 1:05:01 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 8, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors
1891 James Blair set stake and tile at intersection of both 1/4 lines
1972 Kenneth Suydam "Found Iron"
1975 I found a iron pipe in the pavement which was 0.83 East & 1.01 South of intersection of 1/4 lines
1977 I found a iron pipe in the pavement which checked K. Suydam's witnesses and recorded it in Liber 4, Page 205
1984 I found a iron pipe in the pavement
1998 Found iron pipe in the pavement and witnessed prior to road re-construction. 1/2" capped re-rod burried in field on 1/4 line North 34.96. NW corner of house foundation S 65 E 235.63. Survey mark spike & re-mon tag in post South 38.05. Dbl hd nail & re-mon tag in EP N 80 W 68.82

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 8, 1999 Found strap iron (railroad strap rail) and pieces of tile 20" deep under new asphalt pavement. Replaced strap iron with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

dbl. hd. nail and re-mon tag in E.P. N 80° W 68.85
1/2" X 24' re-rod (12" deep) capped GER 13040 on 1/4 line North 34.94
NW corner of house foundation S 65° E 235.61
Survey mark spike and re-mon tag in post South 38.08



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 3, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040