

JAN 5 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7-S R 4-E F-12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 6, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors
1886 James Blair found stake 4 1/8 links south of line between E & W 1/4 corners and used line between E & W 1/4 corners.
1897 James Blair found stake
1984 I reestablished the corner by setting a 3/4" iron pipe in the pavement on line between the E & W 1/4 corners proportionate to Blairs record distance between the 1/4 corners and recorded it in Liber 5 Page 127
1994 Steve Young found iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 6, 1999 Found 3/4" iron pipe 20" below new asphalt pavement. Drove the pipe down with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

dbl. hd. nail & disc in E.P. S 70° W 80.27
Iron pipe on property line N 70° W 95.85
SE corner house N 20° W 69.07
Iron pipe on 1/4 line to North 1/4 corner North 33.00

The corner is 3'± south of north edge of the pavement

LIBER 1 PAGE 383
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

7 DEC 1999 1:05:27 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 1, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040