

SURVEY & REMONUMENTATION

FEB 16 1999

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 293

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

10 DEC 1998 9:45:22 AM

VICTORIA J. DANIELS
 REGISTER OF DEEDS

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 7 - S R - 4 - E	G-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on September 09, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1819 Joseph Fletcher set post corner Sec.'s 27, 28, 33, & 34 W. Ash 12 N 72 W 12 W. Oak 30 N 85 E 22
 1878 James Blair found stake & bricks
 Early 1900's J. L. Richards records called for "stake, stone & bricks" & "stake & bricks"
 1964 I dug and found a piece of strap iron and set a 1" X 12" iron pipe over the strap iron
 1973 I found the iron pipe and recorded it in L 2 P 541

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 9, 1998 I found 1" X 15" iron pipe over two pieces of strap iron, a horse shoe and small traces of brick. Replaced the iron pipe with a 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 and placed a monument box in newly layed asphalt pavement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Fd. dbl hd nail & disc in E.P. North 31.95
 Survey mark spike in Elec. pole S 10° W 141.45
 Face of Top bolt (4'± above ground) in SE leg of steel tower N 60° W 223.53
 Combination stop sign & road sign post S 75° W 45.68



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 22, 1998

Signed by Glenn E. Richard Date Nov. 10, 1998
 Glenn E. Richard

Surveyor's Michigan License No. 13040